

土量計算書

路線名【市道原高牟礼線】

工区名【 】

様式1-2

測点	単距	断面積					平均断面積					立積					
		片切掘積 人併用機	片切掘積 人併用機	切土整形 BH整形	切土整形 BH整形	植生工	片切掘積 人併用機	片切掘積 人併用機	切土整形 BH整形	切土整形 BH整形	植生工	片切掘積 人併用機	片切掘積 人併用機	切土整形 BH整形	切土整形 BH整形	植生工	
		軟岩	普通土	軟岩	普通土	人力	軟岩	普通土	軟岩	普通土	人力	軟岩	普通土	軟岩	普通土	人力	
No.3	0.00	0.00															
No.3+10.0	10.00	30.50	30.50		9.90		15.25					152.5					
No.4	10.00		19.30		8.50		24.90			9.20			249.0			92.0	
+10.0	10.00		9.00		6.50	5.90	14.15			7.50			141.5			75.0	
No.5	10.00		7.10		6.10	5.30	8.05			6.30	5.60		80.5			63.0	56.0
BC-4	2.25		7.00		6.60	5.70	7.05			6.35	5.50		15.9			14.3	12.4
SP-4	6.84		5.80		7.10	6.20	6.40			6.85	5.95		43.8			46.9	40.7
EC-4	6.84		1.90		2.50	1.60	3.85			4.80	3.90		26.3			32.8	26.7
No.6	4.07		1.40		1.70	0.90	1.65			2.10	1.25		6.7			8.5	5.1
+10.0	10.00		17.30		8.70	8.00	9.35			5.20	4.45		93.5			52.0	44.5
No.7	10.00		17.00		8.00	7.20	17.15			8.35	7.60		171.5			83.5	76.0
BC-5	7.52		6.60		6.40	5.50	11.80			7.20	6.35		88.7			54.1	47.8
+15.0	7.48		0.00		0.00	0.00	3.30			3.20	2.75		24.7			23.9	20.6
合計	95.00												152.5	942.1		546.0	329.8