

土量計算書

工事名【鹿島掛腰線舗装工事】

様式1

測点	単距	断面積	幅員			平均断面積	平均幅員			立積	面積		
		掘削	表層工	路盤工	舗装版破碎	掘削	表層工	路盤工	舗装版破碎	掘削	表層工	路盤工	舗装版破碎
		機械	t=5cm	t=15cm	As	機械	t=5cm	t=15cm	As	機械	t=5cm	t=15cm	As
No.10	0.00	1.2	4.50	4.50	4.50								
No.11	20.00	0.9	4.50	4.50	4.50	1.05	4.50	4.50	4.50	21.0	90.0	90.0	90.0
No.11+13.0	13.00	0.9	4.50	4.50	4.50	0.90	4.50	4.50	4.50	11.7	58.5	58.5	58.5
No.12	7.00	0.9	4.50	4.50	4.55	0.90	4.50	4.50	4.53	6.3	31.5	31.5	31.7
No.13	20.00	1.0	4.50	4.50	4.45	0.95	4.50	4.50	4.50	19.0	90.0	90.0	90.0
No.14	20.00	1.1	4.50	4.50	4.45	1.05	4.50	4.50	4.45	21.0	90.0	90.0	89.0
No.15	20.00	1.2	4.50	4.50	4.45	1.15	4.50	4.50	4.45	23.0	90.0	90.0	89.0
No.15+18.0	18.00	1.0	4.50	4.50	4.45	1.10	4.50	4.50	4.45	19.8	81.0	81.0	80.1
No.16	2.00	1.2	4.50	4.50	4.30	1.10	4.50	4.50	4.38	2.2	9.0	9.0	8.8
No.17	20.00	1.1	4.50	4.50	4.60	1.15	4.50	4.50	4.45	23.0	90.0	90.0	89.0
No.18	20.00	1.1	4.50	4.50	4.50	1.10	4.50	4.50	4.55	22.0	90.0	90.0	91.0
No.19	20.00	1.2	4.50	4.50	4.40	1.15	4.50	4.50	4.45	23.0	90.0	90.0	89.0
No.20	20.00	1.1	4.50	4.50	4.50	1.15	4.50	4.50	4.45	23.0	90.0	90.0	89.0
No.21	20.00	1.1	4.50	4.50	4.45	1.10	4.50	4.50	4.48	22.0	90.0	90.0	89.6
小計	220.00									237.00	990.00	990.00	984.70